

**NOTICE TO CONTRACTORS  
HIGHWAY CONSTRUCTION****June 19, 2017**

Bidding proposals may not be issued to bidders unless they are prequalified, except where otherwise provided in Plans and Specifications. For those contractors who are not prequalified, application for prequalification will be submitted on DOT Form 420-010 (Standard Questionnaire and Financial Statement) and must be received by the Prequalification Engineer no less than fifteen days prior to the scheduled bid opening to receive consideration for issuance of a bidding proposal for that bid opening. Informational copies of plans and specifications are on file in the office of the County Engineer of the County in which the work is situated, the chapter offices of the Associated General Contractors of America, the offices of the Regional Administrators or the Headquarters of the Department of Transportation, and at [www.wsdot.wa.gov/biz/contaa/](http://www.wsdot.wa.gov/biz/contaa/) where they may be inspected. The use of informational proposals shall be allowed only upon written request and will be accepted only when written authority for their use has been granted. **ESTIMATE RANGES PUBLISHED IN THIS NOTICE MUST NOT BE USED AS A BASIS FOR BID PREPARATION.**

All bid proposals shall be accompanied by a bid proposal deposit in cash, certified check, cashier's check or surety bond in an amount equal to five percent (5%) of the amount of such bid proposal. Should the successful bidder fail to enter into a contract and furnish a satisfactory performance bond, the bid proposal deposit shall be forfeited. **Bonds submitted on other than the bond form provided by the department may be subject to rejection. The right is reserved to reject any and all bids and to waive informalities in the bidding.** Sealed bids will be received in the Bid Room 2D20, located on the second floor of the Department of Transportation, 310 Maple Park Avenue SE, Olympia, Washington, 98501 until 11:00:59 am Pacific Time, or at P.O. Box 47360, Olympia, Washington, 98504-7360, until 11:00:59 am Pacific Time or electronically via BidX.com until 11:00:59 am Pacific Time, on the dates shown below except where otherwise provided in the Plans and Specifications.

**FEE: Project Documents will be furnished for the non-refundable fee Plus Sales Tax of:**

<b>Electronic – plans only \$10</b>	<b>Electronic – with proposal \$15</b>	
<b>Paper – one volume \$35</b>	<b>Paper – two volumes \$50</b>	<b>Paper – three volumes \$100</b>

*(Remittance may be made to the Department of Transportation Cash Receipts, Transportation Building, and P.O. Box 47305, Olympia, WA 98504-7305) TO ORDER PLANS AND SPECIFICATIONS PLEASE CALL (360) 705-7835. To order by e-mail, the address is: [CAA@wsdot.wa.gov](mailto:CAA@wsdot.wa.gov).*

***Electronic Project Plans, Specifications, Geotechnical Reports, Addenda, Planholders Lists, Award/Bid Results, and Bid Tabulations are available on the Internet at: <http://www.wsdot.wa.gov/biz/contaa>***

**SMALL WORKS ROSTER:** The Department of Transportation is soliciting contractors interested in qualifying for placement on the department's Small Works Roster. The small works roster process as authorized by RCW 39.04.155 and WAC 468-15 may be used to secure bids for the Agency's small works projects with a total cost less than \$300,000. Contractors that are currently Prequalified may be placed on the Small Works Roster by completing the Small Works Roster Supplement located on the Contract Ad & Award website. For contractors who are not currently prequalified, application for prequalification for small works roster shall be submitted on DOT Form 420-020 (Small Works Questionnaire). Both forms are available by emailing [prequal@wsdot.wa.gov](mailto:prequal@wsdot.wa.gov) or can be printed from the WSDOT Contract Ad & Award website at: <http://www.wsdot.wa.gov/biz/contaa/prequal/default.htm> Applications for placement on the Department of Transportation Small Works Roster will be accepted by emailing [prequal@wsdot.wa.gov](mailto:prequal@wsdot.wa.gov)

**Title VI Notice to Public**

It is the Washington State Department of Transportation's (WSDOT) policy to assure that no person shall, on the grounds of race, color, national origin or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated, may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For additional information regarding Title VI complaint procedures and/or information regarding our non-discrimination obligations, please contact OEO's Title VI Coordinator Oscar Cerda at (360) 705-7082.

**Americans with Disabilities Act (ADA) Information:** This material can be made available in an alternate format by emailing the WSDOT Diversity/ADA Affairs team at [wsdotada@wsdot.wa.gov](mailto:wsdotada@wsdot.wa.gov) or by calling toll free, 855-362-4ADA(4232). Persons who are deaf or hard of hearing may make a request by calling the Washington State Relay at 711.

## **BID OPENING WEDNESDAY, JUNE 21, 2017**

- \*1. (CLARK) **ATIS INFILL – I/S BYPASS 4<sup>TH</sup> PLAIN TO MAIN ST** (CL 41, \$700,000 - \$750,000)  
\*\*\* **CONTAINS CONDITION OF AWARD DBE GOAL: 4%**. F.A. No. CM-0503(031) on SR 503, MP 0.00 to MP 8.18. Requires: Installing ITS communication conduit systems, ITS communication cables and interfaces, closed circuit television systems, ITS video/data transmission and distribution systems, variable message sign system, license plate reader systems, traffic control and other work. 35 Working days. Involves 19 items. 15 T CSBC, 75 LF beam guardrail. Lump Sum Bids for: Cantilever sign struct, ITS comm conduit sys, ITS comm cables & interfaces, ITS CCTV sys, ITS video/data dist & trans sys, VMS sys, ITS license plate reader sys, temp traffic control, SPCC plan. (QL-0088)(450317Q)(16X322)(9116)(3 of 3)(1)
- \*2. (COWLITZ) **COWLITZ RIVER BRIDGE NO. 432/10S REPAIR AND OVERLAY** (CL 6, \$750,000 – \$1,000,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 9%**. F.A. No. NHPP-0432(023) on SR 432, MP 9.72 to MP 9.89. Requires: Scarifying concrete surface, performing further deck preparation, furnishing, placing, finishing and curing modified concrete overlay, modifying bridge drains, modifying expansion joints for one bridge, traffic control and other work. 25 Working days. Involves 42 items. 3600 CF mod conc overlay, 2160 SY finish and cure mod conc overlay, 31 LF exp jnt mod strip seal, 2160 SY scarify conc surface, 500 SF further deck prep – exist repair material, 280 LF seal exist longitudinal and transverse jnt, 1500 SY plane bit pvmt, 52 T HMA CL 3/8 IN PG 64-22, 6 DAY ESC lead, 1350 LF temp barrier, 2775 LF plastic line, 3700 LF temp pvmt marking – short duration, 334 HR other traffic control labor, 634 SF const signs CL A. Lump Sum Bids for: Temp traffic control, pedestrian traffic control, struct survey, SPCC plan. (XL-4965)(443214B)(17X313)(9117)(3 of 3)(3)

## **BID OPENING WEDNESDAY, JUNE 28, 2017**

- \*1. (SNOHOMISH) **MUKILTEO FERRY TERMINAL (PHASE 2) TRESTLE & BRIDGE SEAT CONSTRUCTION** (CL 6, \$6,000,000 - \$7,500,000) a Federal Transit Authority Project WA-2017-007-00 & WA-2017-023-00 on SR 525, MP 8.47 Vicinity for Washington State Ferries. **CONTAINS APPRENTICE UTILIZATION REQ: 15%**. Requires: Constructing a trestle and bridge seat foundation, slope stabilization, selected demolition, pedestrian trail establishment, traffic control and other work. 185 Working days. Involves 86 items. 15 CY rdwy excav incl haul, 325 T quarry spalls, 735 T armor stone, 168 T bedding stone, 160 CY fish mix, 3700 SF geotextile filter fabric, 58 LF trench drain, 140 LF sanitary sewer pipe, 90 LF water pipe with insulation, 427000 LB epoxy-coated st rebar, 190 CY conc CL 5000, 1500 CY conc CL 6000, 320 CY conc within CFST pile, 53 EA driving CFST pile, 8 EA CFST dynamic pile testing, 35 EA conical pile tip, 405 LF temp bridge rail, 58 LF seismic jnt, 132 EA driving st HP piling, 300 CY excav within CFST pile incl haul, 1306 T CSBC, 2118 SY plastic covering, 167 SY stabilized const entrance, 550 LF turbidity curtain, 1410 HR flaggers, 199 SF const signs CL A, 483 HR other traffic control labor, 25 EA bubble curtain, 4236 SY const geotextile, 4 EA life ladder, 5 EA bollard, 30 EA beam sleeve, 18 EA slab sleeve, 54 EA slab sleeve seal. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Struct st, environmental compliance lead, temp traffic control, marine survey, furnish bubble curtain sys, general electrical, transporting prefab pile, under trestle water and sanitary sewer casings, shoreline protection survey, SPCC plan. (XL-4681)(904433A)(16W125)(9118)(4 of 4)(1)
- \*2. (KITTTAS) **1.5 MILES E OF CABIN CREEK RD TO KACHESS RIVER VIC –PAVING** (CL 4, \$750,000 - \$1,000,000) **CONTAINS VOLUNTARY MSVWBE GOAL: 26%**. A State Project on I-90, MP 65.54 to MP 69.04 Westbound and MP 66.00 to MP 67.35 East Bound. Requires: Planing bituminous pavement, HMA paving, pavement markings and delineation, traffic control and other work. 15 Working days. Involves 34 items. 850 SY pvmt repair excav incl haul, 5 T asph, 20920 SY plane bit pvmt, 3290 T HMA CL 3/8 IN PG 64-28, 9150 LF longitudinal jnt seal, 25080 LF jnt adhesive bit pvmt, 21690 LF grooved paint line, 8160 LF grooved plastic line, 3 MI shoulder rumble strip, 8160 LF temp pvmt marking-short duration, 72 SF const signs CL A. Lump Sum Bids for: Temp traffic control, SPCC plan. (XL-5436)(509016Z)(17Y007)(9120)(2 of 2)(1)

## **BID OPENING THURSDAY, JULY 6, 2017**

- \*1. (SPOKANE) **DEER RD TO COLBERT CORRIDOR IMPROVEMENTS AND PAVING** (CL 4 or 17 & 27, \$4,000,000 - \$5,000,000) **CONTAINS VOLUNTARY SMALL BUSINESS ENTERPRISE (SBE) GOAL 10% WITH MANDATORY SBE INCLUSION PLAN** F.A. No. NHPP-0002(848) on US 2, MP 296.81 to MP 299.91. **CONTAINS APPRENTICE UTILIZATION REQ: 15%**. Requires: Planing bituminous pavement, paving with HMA, concrete curb, sidewalk, and traffic islands, driveway approaches, adjusting utilities, drainage and storm sewer, pavement markings, guide post, illumination system, traffic signal system, permanent signing, traffic control and other work. 60 Working days. Involves 102 items. 1345 CY common borrow incl haul, 1215 CY embank compact, 36 EA Spokane county curb, 10 EA catch basin cover, 455 LF sch A storm sewer pipe, 805 T CSBC, 113500 SY plane bit pvmt, 11630 T HMA CL ½ IN PG 70-28, 52100 LF jnt adhesive, 11 ACRE seed, fert, mulch, 1259 LF cement conc traffic curb & gutter, 8890 LF mod cement conc extruded curb, 1282 SY cement conc traffic island, 4 EA beam guardrail non-flare term, 64475 LF paint line, 21791 LF grooved plastic line, 4962 LF grooved plastic wide line – dotted extension, 11050 LF painted wide lane line, 12772 LF grooved plastic wide lane line, 1716 SF grooved plastic crosswalk line, 36 EA grooved plastic traffic arrow, 65300 LF temp pvmt marking-short duration, 3104 SY cement conc sidewalk, 504 SY cement conc driveway entrance, 17 EA cement conc curb ramp. Lump Sum Bids for: Perm signing, cantilever sign struct, illum sys, traffic signal sys, ITS elec speed limit sign, temp traffic control, ped traffic control, rdwy survey, ADA features survey, SPCC plan.(XL-5156)(600206B)(17Z001)(9124)(2 of 3)

## **BID OPENING WEDNESDAY, JULY 12, 2017**

1. (YAKIMA) **SELAH CREEK BRIDGE EB – PAVING & BRIDGE JOINT REPAIR** (CL 4 or 6, \$500,000 - \$600,000) **CONTAINS VOLUNTARY SMALL BUSINESS ENTERPRISE (SBE) GOAL 10% WITH MANDATORY SBE INCLUSION PLAN** F.A. No. HBP-0082(012) on I-82 MP 23.88 to MP 24.15. Requires: Removing existing overlay, bridge deck repair, waterproofing membrane, expansion joint modification, paving with HMA, traffic control and other work. 20 Working days. Involves 21 items. 78 LF expansion jnt mod, strip seal & HDR replace, 254 SF bridge deck repair, 5650 SY waterproof membrane, 5650 SY remove exist overlay, 363 SY plane bit pvmt, 880 T HMA CL ½ IN PG 64-28, 4270 LF temp pvmt marking – short duration. Lump Sum Bids for: Temp traffic control, struct survey, SPCC plans. (XL-5437)(508209O)(17Y008)(9126)(1 of 3)

## **BID OPENING THURSDAY, JULY 13, 2017 – OPENS IN EASTERN REGION**

1. (SPOKANE) **NSC – HAZARDOUS MATERIAL SITE ABATEMENT – OXARC** (CL 45, \$600,000 - \$750,000) **CONTAINS VOLUNTARY MSVWBE GOAL: 26%** A State Project on US 395, MP 160.34 to MP 160.46. Requires: Mercury and carbide lime excavation including haul, inlet protection, erosion and sediment control, stabilized construction entrance, tire wash, street cleaning, contour grading and other work. 25 Working days. Involves 14 bid items. 705 CY mercury excav incl haul, 21000 CY carbide lime excav incl haul, 170 CY CSBC, 250 SY stabilize const entrance, 1 EA tire wash, 1625 LF high vis fence. Lump Sum Bids for: SPCC plan. (RW-5106)(600013A) (17Z019)(-)(1 of 3)

## **BID OPENING THURSDAY, JULY 19, 2017**

### **PRE-BID SITE VISIT**

The Contracting Agency will hold one pre-bid site visit of Bridge No. 90/25S for interested proposal holders and planholders. Proposal holders and planholders shall make reservations at the Project Engineer's Office by phone or e-mail no later than two business days in advance of the site visit: Dave Schrader Phone: (425)225-8734 E-mail: [SchradD@wsdot.wa.gov](mailto:SchradD@wsdot.wa.gov) Because of limited access to Bridge No. 90/25S, prospective bidders will only be allowed on the bridge during the pre-bid site visit conducted by the Project Engineer. Questions will be addressed as described in Section 1-02.4. The site visit will take place 10:00 AM Wednesday June 28, 2017 and prospective bidders shall meet at the West I-90 Lid Park located at 2310 West Mercer Way, Mercer Island, WA 98040. Prospective bidders will be transported to the bridge and back by WSDOT staff. Hard hat, safety vest, and appropriate clothing for moving around the bridge structure will be required. All planholders are encouraged to attend.

(KING) **LACEY V MURROW BRIDGE ELECTRICAL REHABILITATION** (CL 16, \$400,000 - \$600,000) **CONTAINS VOLUNTARY SMALL BUSINESS ENTERPRISE (SBE) GOAL 10% WITH MANDATORY SBE INCLUSION PLAN** F.A. No. NHPP-0901(498) on I-90, MP 4.21 to MP 4.73.

Requires: Replacing the medium voltage switchgear, grounding the electrical distribution system, grounding existing fence, traffic control and other work. 75 Working days. Involves 17 items. Lump Sum Bids for: Temp traffic control, field measure, wire & cable, raceway, pontoon cell wall and ceiling drill, switchgear, grounding, testing & commissioning, maintenance manuals, training and as-built drawings, SPCC plan.(XL-5187)(109024Q)(17A003)(9121)(1 of 4)

2. (GRAYS HARBOR, JEFFERSON, KITSAP, MASON, PIERCE, THURSTON) **2017 OLYMPIC REGION GUARDRAIL AND CABLE BARRIER** (CL 11, \$1,000,000 - \$2,000,000) **CONTAINS VOLUNTARY SMALL BUSINESS ENTERPRISE (SBE) GOAL 10% WITH MANDATORY SBE INCLUSION PLAN**. Requires: Removing beam guardrail, cable barrier and anchors, placing crushed surfacing, raising beam guardrail, installing beam guardrail, anchors, transitions, high tension cable barrier, precast concrete barrier, guideposts and barrier delineators, traffic control and other work. 60 Working days. Involves 33 items. 45 T CSBC, 59 SY seed & fert by hand, 3777 LF beam guardrail, 13 EA beam guardrail non-flared term, 1139 LF beam guardrail buried term, 11760 LF raise exist beam guardrail, 263 LF precast conc barrier, 22040 LF high-tension cable barrier sys, 239 EA flex guidepost. Lump Sum Bids for: Additional high-tension cable barrier components, temp traffic control, SPCC plan. (XL-5115)(300015T)(16C504)(9123)(1 of 4)

Projects awarded the week of June 12, 2017.

(Lewis) Coal Creek Bridge to Gulch Bridge - Paving - #9113 – Lakeside Industries, Inc., Centralia, WA 98531-1961 - \$3,327,442.40

(Clark) SR 503 to NE 4<sup>th</sup> Plain Blvd Paving - #9111 – Granite Construction Company, Vancouver, WA 98684-7506 - \$3,264,264.00

(Chelan) Coles Corner Vicinity Safety Improvements - #9101 – Taylor’s Excavators, Inc., Stanwood, WA 98292-4531 - \$703,078.00

Roger Millar  
**Secretary of Transportation**

- \* Previously Advertised
- \*\* Extended
- \*\*\* Revised