



May 5, 2016

TO: Marco Foster, MS47354

THRU: Madden / K. Klingman, NB82-230

FROM: P. Fuller / S. Beadle, NB 82-66

SUBJECT: C8549

SR99, AWV Replacement North Access Connection

F.A. Project No: STPF-0099(122)

CHANGE ORDER 133

Ductbank Changes EN1, EN3, EN4 & EP5

Attached for your review, approval and further processing is HQ executed Change Order #133 "Ductbank Changes EN1, EN3, EN4 & EP5", for the subject project. Change Order Checklist is attached (Attachment A).

Description of the Change

The change order compensates the Contractor for added work and extended overhead associated with new work. This change order revises ductbanks EN1 & EN4, EN3 and adds new ductbank EP5.

1. EN1 and EN4 Ductbanks:

Revises the horizontal and vertical alignment of ductbank EN1 as shown on UPAL1, UP1 and UPR7. This work will:

- Raise EN1 vertical alignment to be above new ductbank EP5 and above EN2 and EN4 as shown on UPD33 and UPD33A.
- Revise the horizontal alignment of EN1 to run along the Substation Yard retaining wall foundation.
- Compensate the Contractor for the added effort and complexity for working along the SCL Substation retaining wall as shown on UPD33 and UPD33A.
- Demolish and replace 10 ft. of existing EN1 duct bank to tie into the new alignment. This change order compensates the Contractor for demolishing and constructing 10 ft. of ductbank.
- Compensate the Contractor for re-trenching, re-shoring and backfilling a second time for EN1. It also covers additional costs for vactoring and supporting live communication power and other utilities.

Marco Foster C8549 CO133 May 5, 2016 Page 2 of 4

- Add new reinforcement cage to EN4 per SCL Guideline U2-11.2 as shown on UPR10.

2. EN3 Ductbank:

Revises the horizontal and vertical alignments of ductbank EN3 as shown on UPAL1, UP1, UP8, UPR8, UPR9, UPD11 and UPD33.

This change order compensates the Contractor for re-trenching, re-shoring and backfilling a second time at EN3. The change order also covers additional costs for vactoring and supporting in place existing utilities.

This change order makes ductbank adjustments to avoid future King County ductbank as shown on UPR9.

3. EP5 Ductbank:

Adds new ductbank EP5 feeders from Station EP5 350+00.00 to 350+10.86 to the SCL Substation yard as shown on UPAL1, UP1, UPR7-UPR9, UPR10, UPD20, UPD33. New ductbank EP5 shall be positioned in between ductbanks EN1 and EN3 and ductbanks EN4 and EN2.

Development of the Change

The Development of Change will follow the numbering system as above.

1. Constructability issues with the planned alignment of the EN1 ductbank which was in conflict with the substation wall footing were brought to the attention of the PE in RFI#380. The original plan shows that the bottom of the footing is below EN1. The work was stopped and SCL began to redesign the alignment for EN1. The redesign captured the protection and support of the substation retaining wall. The updated plan clearly shows that the bottom of the duct bank is near the bottom of the footing for the wall. The new design also included approximately ten feet of new ductbank to replace previously installed EN1 duct bank that needed to be removed so that it can be installed above the added duct bank EP5. Since the work had stopped and Contractor could not continue work until SCL provided new plans, approximately half of 80 feet of EN1 was backfilled. The Contractor had to re-excavate the trench and re-shore it. The design also captured profile changes per RFI#413 where EN1 alignment was in conflict with a King County vault at the SW corner of 6th Ave and Harrison St. The new alignment will reroute EN1 to avoid the vault. Other profile changes include vertical changes in profile from 300 foot sweeping radii to four vertical profile changes with two 50 foot radii and two 30 foot radii. There were also minor changes that SCL wanted to address at EN4 ductbank where is crosses ED1. The plans did not show a reinforcement cage which is standard practice when ductbanks cross over each other. This reinforcement cage was added in the revised plans.

Marco Foster C8549 CO133 May 5, 2016 Page 3 of 4

- 2. While excavating for EN2 ductbank, the Contractor noticed that the planned EN3 ductbank could not be installed due to a conflict with an existing SCL vault at the SW comer of 6th Ave and Harrison St. as referenced in RFI#398. The planned configuration for EN1, EN4, EN2 and EN3 is shown as being constructed side by side in order listed. During the redesign, the new King County ductbank which runs parallel to Harrison St. was discovered to be in conflict with the new alignment of EN3. The result, EN3 was designed to have a splayed ductbank to avoid the top of new King County Ductbank. EN3 also includes costs to re-trench and re-shore a portion of the alignment from M30 vault to M9 vault. This ductbank trench was backfilled when the conflict with the SCL vault was encountered.
- 3. In RF1#371, the Contractor discovered an unknown ductbank crossing the EN4 alignment which runs north-south across Harrison at approximately at Station H-Line 96+15. After investigating, the unknown ductbank was found to be empty and was removed. In further discussions, SCL wanted to make this reconnection as EP5 into Vault M9 which the original plans did not include. Without this connection, SCL could not power up the new EP1 ductbank. The new design of EP5 was placed on top of EN2, EN4 ductbanks and in the bottom of new designed elevations of EN1, EN3 ductbanks.

We received plans from SCL on December 23, 2015. These plans were forwarded to the Contractor the same day. Upgrades required by SCL to meet current standards and future demands contributed to the cost increase. Work stopped for EN1 and EN3 until agreement was reached on the negotiated pricing. The plans also included the new work for EP5. This added work is being paid for by SCL.

Schedule Analysis

This change order is adding 28 working days to the contract due to the added work described above. There are overhead costs associated with these added working days. We performed an independent schedule analysis and agree to the number of added working days. See *Attachment E*. We compared the baseline work activities with the revised January 2016 schedule provided by the Contractor. The schedule shows a 35 day difference for a composite of changes involving EP5, EP1, EP2, EP3, EP4, EN3, and EN4. The analysis included all of EP1, EP2, EP3 and EP4 because the Contractor had combined all these ductbanks together in the baseline. We performed a combined schedule analysis with both CO133 and CO147 due to the difficulty in separating the activities. We agreed with the increase of 28 working days for CO133. The Contractor also incurred 7 additional working days on CO147 which totals 35 working days and this agrees with our independent analysis. The work included in this change order is on the critical path of the approved schedule.

Approvals

- PE Approval—Patrick Fuller gave approval on 4/29/2016 (Attachment B).
- Region Approval—Tom Madden gave approval on 5/3/2016 (Attachment B).
- HQ Approval—Marco Foster gave approval on 5/2/2016 (Attachment B).
- FHWA Approval—Anthony Sarhan gave approval on 5/2/2016 (Attachment B).

Marco Foster C8549 CO133 May 5, 2016 Page 4 of 4

- Program Management—Mario Mathisen gave approval on 5/3/2016(Attachment B).
- Engineer of Record—Monica Moravec signed plan sheets 12/22/20159(See change order plans)
- City Funding Approval-Jon Gray approved direct costs on 3/4/2016 and approved extended overhead costs on 3/17/2016. (See Attachment B).

Entitlement & Price

The Contractor will be reimbursed for the added work as stated in the change order. The costs include both direct and indirect cost, including extended overhead for this added work. The Contractor will be compensated for the described added work that affected the critical path. The increased costs included retrenching costs for EN1 and EN3, the difficulty to shore and excavate along the substation for EN1, to rebuild a portion of the EN1ductbank to tie in to the new alignment, and to build new ductbank EP5. The Contractor will be compensated for the described added work that affected the critical path. This change order is a negotiated amount of \$511,217.11, which includes added direct and extended overhead costs associated with an added 28 working days to the contract. (See Estimate – Attachment C).

Contract Time

This change order adds 28 working days to the contract. There are no changes to contract interim completion dates as a result of this change order.

PF: jp Attachments

cc: File 8549 3(133)

DATE: 05/06/16
Page 1 of \5

FEDERAL AID NO: STPF-0099 (122)

SR 99, ALASKAN WAY VIADUCT - REPLACEMENT NORTH ACC CONTRACT TITLE: CHANGE ORDER NO: 133 R1 EN1, EN3, EN4, EP5 DUCTBANK CHGS. PRIME CONTRACTOR: GUY F. ATKINSON CONSTRUCTION, LLC. 707 SOUTH GRADY WAY STE 500 RENTON WA 98057-3224 (X) Ordered by Engineer under the terms of Section 1-04.4 of the Standard Specifications () Change proposed by Contractor **ENDORSED BY:** SURETY CONSENT: ATTORNEY IN FACT DATE ORIGINAL CONTRACT AMOUNT: 41,640,622.60 **CURRENT CONTRACT AMOUNT:** 47,557,143.79 511,217.11 **ESTIMATED NET CHANGE THIS ORDER:** 48,068,360.90 **ESTIMATED CONTRACT TOTAL AFTER CHANGE:** Approval Required: () Region () Olympia Service Center () Local Agency () EXECUTED EXECUTED: STATE CONSTRUCTION ENGINEER PROJECT ENGINEER OTHER APPROVAL WHEN REQUIRED APPROVAL RECOMMENDED () EXECUTED Laones Olay Madde

CONTRACT NO:

008549

DATE: 05/06/16 Page 2 of 15

CONTRACT NO: 008549

CHANGE ORDER NO: 133 R1

All work, materials, and measurements to be in accordance with the provisions of the Standard Specifications and Special Provisions for the type of construction involved.

This contract is revised as follows:

DESCRIPTION

The change order compensates the Contractor for added work and extended overhead associated with new work. This change order revises ductbanks EN1 & EN4, EN3 and adds new ductbank EP5.

EN1 and EN4 Ductbanks:

Revises the horizontal and vertical alignment of ductbank EN1 as shown on UPAL1, UP1 and UPR7. Raises EN1 vertical alignment to be above new ductbank EP5 and above EN2 and EN4 as shown on UPD33 and UPD33A. Revises horizontal alignment to run along the Substation Yard retaining wall foundation. This change order compensates the Contractor for the added effort and complexity for working along the SCL Substation retaining wall as shown on UPD33 and UPD33A.

Demolishes and replaces 10 ft. of installed EN1 duct bank to tie into the new alignment. This change order compensates the Contractor for demolishing and constructing 10 ft. of new ductbank.

This change order compensates the Contractor for re-trenching, re-shoring and backfilling a second time for EN1. It also covers additional costs for vactoring and supporting live communication power and other utilities.

Adds new reinforcement cage to EN4 per SCL Guideline U2-11.2 as shown on UPR10.

EN3 Ductbank:

Revises the horizontal and vertical alignments of ductbank EN3 as shown on UPAL1, UP1, UP8, UPR8, UPR9, UPD11 and UPD33.

This change order compensates the Contractor for re-trenching, re-shoring and backfilling a second time at EN3. The change order also covers additional costs for vactoring and supporting in place existing utilities.

This change order makes ductbank adjustments to avoid future King County ductbank as shown on UPR9.

EP5 Ductbank:

Adds new ductbank EP5 feeders from Station EP5 350+00.00 to 350+10.86 to the SCL Substation yard as shown on UPAL1, UP1, UPR7-UPR9, UPR10, UPD20, UPD33. New ductbank EP5 shall be positioned in between ductbanks EN1 and EN3 above and duckbanks EN4 and EN2 below.

This change order revises the following plan sheets UPAL1, UP1, UP8,

DATE: 05/06/16 Page 3 of 15

CONTRACT NO: 008549

CHANGE ORDER NO: 133 R1

UPR7-UPR10, UPD11, UPD20, UPD33, and adds the following new plan sheet UPD33A.

MATERIALS

All materials incorporated into the project shall meet the requirements of all the Contract Documents.

MEASUREMENT

Measurement of the new lump sum item, "CO133 EN1, EN3, EN4, EP5 Ductbank Changes", shall be in accordance with Standard Specification 1-09.1, Measurement of Quantities of Lump Sum Items.

PAYMENT

This change order creates a new lump sum item, "CO133 EN1, EN3, EN4, EP5 Ductbank Changes" in the amount of \$511,217.11. This amount shall be full payment for all labor, equipment and materials to perform the work as described above, including but not limited to engineering, planning, scheduling, excavation and shoring, procuring ductbank materials and installing them, placing high strength FTB, forming materials, setting forms and stripping, placing low strength FTB, dirt export and disposal, vactoring, dewatering the excavation area, supporting existing utilities and existing foundations, mobilization and demobilization of equipment, survey, cleanup and overhead for the added work per Section 1-09.1 of the Standard Specifications.

CONTRACT TIME


There are 28 working days added to the contract time as a result of this change order. No changes to contract interim milestones are made as a result of this change order.


DATE:05/06/16 Pag


ge 4 of


	CON	TRACT	NO: 00	08549	CHANGE ORDER NO: 133 R1							
	ITEM NO	ROUP STD ITEM		ITEM DESCRIPTION	UNIT MEASURE	UNIT PRICE	EST QTY CHANGE	EST AMT CHANGE				
461	11/69	08	············	C●133 EN1, EN3, EN4, EP5 DUCTBANK CHANGES	L.S.	0.00	•.00	511,217.11				

511,217.11









SHEET KEY

CONSTRUCTION NOTES:

CONSTRUCTION NOTE REFER TO DRAWING UPN1

GENERAL NOTES:

- ADVANCED NOTIFICATION IS NEEDED BEFORE ANY CONSTRUCTION OCCURS, CALL BEFORE YOU DIG 1-800-424-555S.
- FOR SEATTLE CITY LIGHT UNDERGROUNDING NOTES, LEGEND, AND STRUCTURE NOTES, REFER TO DRAWINGS UPN1-UPN2.
- FOR DUCT BANK ALIGNMENT INFORMATION, REFER TO DRAWINGS UPAL1-UPAL6 AND UPT1-UPT3.


LEGEND

COMMUNICATION CONDUIT


FLUIDIZED THERMAL BACHFILL, PER SECTIONS

DISTRIBUTION CONDUIT

SHEET_7_OF__15_CHANGE ORDER NO.__133_R|
CONTRACT__8549___



TIME	4:37am					REGION NO.	STATE	FED.AID PROJ.NO.
DATE	Dec-21-15							
PLOTTED BY	J.LINEHAN					10	WASH	
DESIGNED BY	S.ZURFLUH					Contract of the Contract of th	UMBER	
ENTERED BY	J.LINEHAN					13/	1003	
CHECKED BY	C.PARK	/2	CO-133: EN3 RELOCATION	12/17/2015	CDP	CONT	RACT NO.	LOCATION NO.
PROJ. ENGR.	S. BEADLE	71	RFI 64 (BASED ON RFI 37 RESPONSE)					XL-3687
REGIONAL ADN	I. T. TREPANIER		REVISION	DATE	BY			XE-0001



KPff Consulting Engineers 1601 Fifth Avenue. Suite 1600 Seattle, Washington 98101–3665 (206) 622–5822 Fax (206) 622–8130




SR 99
ALASKAN WAY VIADUCT-REPLACEMENT
NORTH ACCESS CONNECTION

ENLARGED POWER PLAN

PLAN REF, NO.
UP8

BHIET
211
OF
770
SHEETS



FILE NAME X:\11	10000-11025D\110159 (Alas	skan Way	Viaduct North Access)(CADD\Design\005-MWNA-CPR1.dwg					
TIME	4:40am					REGION	STATE	FED.AID PROJ.NO
DATE	Dec-21-15					40		
PLOTTED BY	J.LINEHAN					10	WASH	
DESIGNED BY	C.PARK	/3\	CO 147: EP3 RELOCATION	12/17/2015	CDP		FEARIN	
ENTERED BY	J.LINEHAN	/2	CO-133: EN3 RELOCATION	12/17/2015	CDP	13 <i>F</i>	1003	
CHECKED BY	S.BARTLETT	1	CO-125: NEW VAULT M-1	12/17/2015	CDP	CONT	RACT NO.	LOCATION NO.
PROJ. ENGR.	S. BEADLE	Sectional	AD1. EN1 PROFILE UPDATE	11/04/2013	CDP			XL-3687
REGIONAL ADM.	T TREPANIER		REVISION	DATE	BV	1		XE-0001





Washington State	
Department of	
Transportation	

SR 99							
ALASKAN	WAY	VIADL	ICT-REP	LACEMENT			
NORT	TH AC	CESS	CONNE	CTION			


SCALE IN FEET HORIZ.

POWER PROFILE

225 0F 770

UPR7

SCALE IN FEET VERT.



SHEET CHANGE ORDER NO. 133 RI CONTRACT 8549

GENERAL NOTES:

- ADVANCED NOTIFICATION IS NEEDED BEFORE ANY CONSTRUCTION OCCURS. CALL BEFORE YOU DIG 1-800-424-5555.
- 2. FOR SEATTLE CITY LIGHT UNDERGROUNDING NOTES, LEGEND, AND STRUCTURE NOTES, REFER TO DRAWINGS UPN1-UPN2.
- 3. FOR DUCT BANK ALIGNMENT INFORMATION, REFER TO DRAWINGS UPAL1-UPAL6 AND UPT1-UPT3.
- WHERE DUCT BANKS CROSS ABOVE PS AND PSD MAINS, INSTALL REINFORCING WITHIN THE DUCT BANK (PER SCL CONSTRUCTION GUIDELINE U2-11.2) A MINIMUM OF 10' BEYOND THE CROSSING
- X CONSTRUCTION NOTE REFER TO DRAWING UPN1



(NAVD) 88

SCALE IN FEET HORIZ.

SCALE IN FEET VERT.

TIME	4:40am					REGION	STATE	FED.AID PROJ.NO.
DATE	Dec-21-15					10	144.611	
PLOTTED BY	J.LINEHAN					10	WASH	
DESIGNED BY	C.PARK						VAMBER	
ENTERED BY	J.LINEHAN		6			13A	1003	
CHECKED BY	S.BARTLETT	/2\	CO-133: EN3 RELOCATION	12/17/2015	CDP	CONTI	TACT NO.	LOCATION NO.
PROJ. ENGR.	S. BEADLE	1	CO-125: NEW VAULT M-1	12/17/2015	CDP			XL-3687
REGIONAL ADM.	T. TREPANIER		REVISION	DATE	BY			712 0001






Washingt on State Department of Transportation


SR 99
ALASKAN WAY VIADUCT-REPLACEMENT
NORTH ACCESS CONNECTION


POWER PROFILE


226 of 770 SHEETE


PLAN PEF. NO UPR8











13.8kV DISTRIBUTION DUCT BANK SECTION

13.8kV DISTRIBUTION DUCT BANK SECTION G

_____ © ALIGNMENT SURFACE RESTORATION: -SEE DETAILS 5, 6, AND 7 ON DRAWING UPD1 DETECTABLE MARKING 3'-0" MIN, TAPE (TYP) OR AS SHOWN ON PROFILES (TYP) LOW STRENGTH FLUIDIZED THERMAL BACKFILL (2)-2" PVC SCH 40 CONDUITS (8)-5" FIBERGLASS CONDUITS HIGH STRENGTH FLUIDIZED THERMAL ENCASEMENT NEAT LINE OF DUCT -BANK EXCAVATION

DISTRIBUTION DUCT BANK SECTION NOTES

- DIMENSIONAL ROUNDING: FOR DUCT BANK WIDTHS/HEIGHTS, DIMENSIONS HAVE BEEN ROUNDED UP TO THE NEAREST INCH. CONTRACTOR IS RESPONSIBLE FOR ENSURING THE BOTTOM, SIDE AND TOP MINIMUM ENCASEMENT DIMENSIONS ARE OBTAINED. ENCASEMENT OVERPOUR SHALL
- 2. ANCHOR SPACERS WITH #4 STEEL REINFORCEMENT AND STEEL WIRE TIES.

SHEET 2 OF 15 CHANGE ORDER NO. 133 RI CONTRACT 85 49

13.8kV DISTRIBUTION DUCT BANK SECTION

PAY OR NEAT LINE

* HSFTB OVERPOUR SHALL NOT EXCEED 6"

(MAX)

FILE NAME X:\110000-110250\110159 (Alaskan Way Viaduct North Access)\CADD\Design\003-MWNA-CPD2.dwg TIME 4:42am FED.AID PROJ.NO. REGION NO. DATE Dec-21-15 10 WASH PLOTTED BY J.LINEHAN **DESIGNED BY** C.PARK 13A003 **ENTERED BY** J.LINEHAN CHECKED BY S.BARTLETT PROJ. ENGR. S. BEADLE 1 CO-133: EN3 RELOCATION XL-3687 REVISION DATE REGIONAL ADM. T. TREPANIER



Pff Consulting Engineers 1601 Fifth Avenue, Suite 1600 Seattle, Washington 98101-3665 (206) 622-5822 Fox (206) 622-8130




SR 99 ALASKAN WAY VIADUCT-REPLACEMENT NORTH ACCESS CONNECTION

241 770


UPD11

POWER DETAILS

NOT EXCEED 6", UNLESS SPECIFICALLY NOTED.



JOB NUMBER 13A003 DESIGNED BY C.PARK ENTEREDBY J.LINEHAN CHECKED BY S.BARTLETT LOCATION NO. /1\CO-133: EN3 RELOCATION PROJ. ENGR. S. BEADLE 12/17/2015 DATE XL-3687 REGIONAL ADM. T. TREPANIER REVISION









NORTH ACCESS CONNECTION

250 0F 770 SHEETS

POWER DETAILS





EP5 DUCT BANK SECTION A SCALE: 1"=2" UP1

SHEET 14 OF 15

CHANGE ORDER NO. 133 K 1

CONTRACT 85 49

FILE NAME X:\110000-110250\110159 (Alaskan Way Viaduct North Access)\CADD\Design\003-MWNA-CPD3.dwg 4:43am FED.AID PROJ.NO. TIME DATE Dec-21-15 10 WASH PLOTTED BY J.LINEHAN **DESIGNED BY** C.PARK 13A003 ENTERED BY J.LINEHAN CHECKED BY S.BARTLETT LOCATION NO. PROJ. ENGR. 12/17/2015 S. BEADLE /1\CO-133: EN3 RELOCATION XL-3687 DATE REGIONAL ADM. T. TREPANIER REVISION




Kpff Consulting Engineers
1601 Fifth Avenue, Suite 1600
Seattle, Washington 98101–3665
(206) 622–5822 Fax (206) 622–8130



SR 99
ALASKAN WAY VIADUCT-REPLACEMENT
NORTH ACCESS CONNECTION

POWER DETAILS

UPD33



SHEET 5 OF 5
CHANGE ORDER NO. 133 R 1
CONTRACT 8549

NEW SHEET

UPD33A

FILE NAME X:\11	0000-110250\110159 (Ala	askan Way	Viaduct North Access)\CADD\Design\003-MWNA-CPI	O3.dwg				
TIME	4:43am	1				REGION NO.	STATE	FED.AID PROJ.NO.
DATE	Dec-21-15					10	WASH	
PLOTTED BY	K.BOSTON					10	WASH	
DESIGNED BY	C.PARK					2.50	UMBER	
ENTERED BY	K.BOSTON					13/	1003	
CHECKED BY	S.BARTLETT					CONT	RACT NO.	LOCATION NO.
PROJ. ENGR.	S. BEADLE	/1\	CO-133: EN3 RELOCATION	12/17/2015	CDP			XL-3687
REGIONAL ADM.	T. TREPANIER		REVISION	DATE	BY			AL-3007







SR 99	
ALASKAN WAY VIADUCT-REPL	ACEMENT
NORTH ACCESS CONNEC	TION

POWER DETAILS

6-SET
263A
0F
770
6-MEETS